

JAWAHARLAL NEHRU UNIVERSITY
ENGINEERING DEPARTMENT
SCHEDULE OF QUANTITY

F.No.4 (34)/E/Q/2021-22/Engg.

Registered Post

23.07.2021

Sealed item rate short quotations are invited from the eligible electrical contractor having valid registration in appropriate class & category in CPWD/MES/Department of telecommunication/Railway/NDMC/Central PSU & Delhi PWD/ Specialized agencies having similar work experience for the work mentioned below, to be received on 30.07.2021 at 3:00 pm in R.No.-141 of Admn. Building, JNU and the same shall be opened at 3:30 pm on the same day.


Name of Work:- Rectification of Fault of Second source of HT breaker installed at Academic Substation for Poorvanchal Area & Tracing of HT Cable fault laid between Academic substation & School of Language (Old Building) at JNU

S. No.	Description of Items	Qty.	Unit	Rate (Rs.)	Amount(Rs.)
1.	Supply & fixing of 11 KV H.T. C.T. of rated 100/5/5 Amp. With wiring connection, testing with primary injection kit, High voltage testing, meggering etc. complete as required.	3.00	Each		
2.	Supply & fixing digital type Amp Ampere Meter of size 96 mm x 96 mm. with wiring connection, testing etc. complete as & when required at site.	2.00	Each		
3.	Tracing of LT cable fault for 1.1 KV grade XPLE/PVC sheathed armoured power cable of size between 120 Sq.mm to 400 sq. mm with help of fault locating machine & cable route finder machine including opening of cable termination, including meggering & High Pressure testing before & after making joints etc as required.	1.00	Job		
4.	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
4.01	300 sq. mm	2.00	Each		
5.	Laying of one number PVC insulated and PVC sheathed/ XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning , protective covering and refilling the trench etc as required.				
5.01	Above 185 sq. mm and upto 400 sq. mm	10.00	Metre		
Total					

Conditions: -

1. The quotation for the work shall remain open for a period of 15 days from the date of opening of quotations. The contractor shall be debarred from the JNU for one year if he withdraw their NIQ before validity period.
2. The work shall be carried out as per specifications/make defined in the NIQ.
3. All taxes shall be deducted as per Govt. of India rules applicable.
4. Time allowed for completion of above work is 07 days. The contractor shall be debarred from the JNU for one year, if contractor fails take up and complete the work within the stipulated period.
5. Earnest Money amounting to **Rs.1619/-** should be deposited in the shape of Pay Order/Banker's Cheque/Demand Draft in favour Finance Officer, JNU. No quotation will be entertained without Earnest Money.
6. **The Quotation and the earnest money shall be placed in separate sealed envelopes, each marked, "Quotation" and "Earnest Money" respectively. Both the envelopes shall be submitted together in another sealed envelope with the name of work and due date of opening written on envelope. The envelopes marked, "Quotation" of only those Quotationers shall be opened, whose earnest money, placed in the other envelope, is found to be in order.**
7. The firm has to produce self attested copies of all relevant documents such as Electrical Contractor License, PAN no., GST Registration and experience certificate along with the quotation.
8. The contractor has to execute the work as per the schedule given by the JNU
9. The quoted rates shall be inclusive of all taxes, cartage etc.
10. Payment shall be made after satisfactory completion of work.


Assistant Engineer (E&M)


Executive Engineer (E)